

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

**SURVEY &  
REMONUMENTATION**

**FEB 08 2001**

DATE 10/10/00 JDB

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

Schoolcraft  
(County)

Located In:

Corner Code #

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/380  
JLV Date 12/19/2000 Time 11:53:24

- |                                    |  |            |
|------------------------------------|--|------------|
| 1. Public Land Survey              | T <u>42N</u> R <u>14W</u>              | <u>G7</u>  |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
| 2. Property Controlling in Section | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
| 3. Miscellaneous Property in Sec.  | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien, in a field survey on 10/25/00, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7							*						
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

April 10, 1851 Algernon Merryweather, DS set section corner Sections 15,16,21,22 Henlock 8 in S30E 8 links Cedar 9 in N60W 22 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct.25, 2000 Thomas P. O'Brien, PS re-established corner by proportionated N and S measurement and in centerline of existing N and S County Road. Set Schoolcraft County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.

Witnesses:

- 6" Cedar N56°E 47.52'
- 6" Aspen S32°E 51.63'
- 8" Balsam S76°W 50.90'
- 4" Aspen N31°W 41.82'
- Carsonite Post S85°E 20.0'



Signed by Thomas P. O'Brien  
Surveyor's Michigan License No. 21274

Date Dec. 12, 2000

LIBER 4 PAGE: 380