

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

DATE 10/10/00 TOB

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &
REMONUMENTATION**

FEB 08 2001

For corners in

Schoolcraft
(County)

Located In:

Corner Code #

SECTION

1. Public Land Survey

T 42N R 14W 69
T _____ R _____
T _____ R _____
T _____ R _____

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/385
JLV Date 12/19/2000 Time 11:53:27

2. Property Controlling
in Section

S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____
S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 10/25/00, ~~to~~ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9							*						
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

April 10, 1851 Algernon Merryweather, DS set section corner Sections 21,22,27,28 Birch 10 in N44E 21 links do 24 in S20W 18 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct.25, 2000 Thomas P. O'Brien, PS re-established corner by proportionated N and S measurement and in centerline of existing County Road. Set Schoolcraft County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.

Witnesses;

10" Spruce N32°W 36.40'

6" Spruce N54°E 46.77'

6" Balsam S45°W 63.02'

4" Cedar S58°E 80.26'

Carsonite Post S85°E 25.0'



Signed by Thomas P. O'Brien

Date Dec. 12, 2000

Surveyor's Michigan License No. 21274

LIBER 4 PAGE: 385