

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

**SURVEY &
REMONUMENTATION**

DATE 10/10/00 JOB

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 08 2001

For corners in

SECTION

Schoolcraft (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>42</u> N R <u>14</u> W	<u>G11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/379
JLO Date 12/19/2000 Time 11:53:23

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 10/24/00, 10 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

April 3, 1851 Algernon Merryweather, DS set section corner Sections 27,28,33,34 Cedar 8 in N30W 11 links Cedar 6 in S50E 18 links

April 22, 1989 Gary E. Koepke, RLS "Found 1/2" iron bar with L.S. Cap No.28406 in center of N-S gravel road, 2646.37' North of East 1/4 corner, Sec.33. Found above witness of record. Accepted corner as found and added witnesses."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct.24, 2000 Thomas P. O'Brien, PS found 1/2" iron bar with partial cap and Koepke witnesses and distance to corner South verify corner position. Accepted iron bar and reset with Schoolcraft County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.

Witnesses:

- 5" Cedar S50°W 36.08'
- 8" Cedar N25°E 49.02'
- 8" Cedar S20°E 57.18' - Koepke BT
- 4" W.Birch S60°W 28.90' -Koepke BT
- Carsonite Post N85°W 20.0'

Thomas P. O'Brien

Signed by Thomas P. O'Brien

Date Dec.12, 2000

Surveyor's Michigan License No. 21274

