

SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED

SURVEY &  
REMONUMENTATION

FEB 08 2001

DATE 10/10/00 JPB LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>14W</u>	<u>G12</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/371  
JLO Date 12/19/2000 Time 11:53:18

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien, in a field survey on 10/30/00, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

April 3, 1851 Algernon Merryweather, DS set 1/4 post Birch 18 in S60W 40 links Hemlock 7 N58E 24 "  
Feb. 16, 1982 Gary E. Koepke, PS "Found iron pin in monument box on existing centerline of U.S. Highway 2 and County Rd., 5282.59 ft. East along 1/4 line from W 1/4 Cor. Sec. 33 and in line with fence line to South.  
Concrete R.O.W. Marker South of Monument Box."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 30, 2000 Thomas P. O'Brien PS found 3/4" iron bar in monument box in centerline US-2 and County Road to North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" iron bar in monument box.  
Witnesses:  
6" Red Pine N34°W 76.88'  
12" White Pine S17°E 79.40'  
Fence Post S62°W 94.95'  
12" Spruce N47°E 122.22'  
Carsonite Post S5°W 50.0'



Signed by Thomas P. O'Brien  
Surveyor's Michigan License No. 21274

Date Dec. 11, 2000