

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

DATE 10/10/00 JPB

SURVEY &
REMONUMENTATION

FEB 08 2001

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft
(County)

Located in:

Corner Code #

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1 LC 4/382
JLO Date 12/19/2000 Time 11:53:25

1. Public Land Survey

T42N R14W H1 ✓
T43N R14W H13

2. Property Controlling
in Section

S ___ T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas P. O'Brien, in a field survey on 11/6/00, 19X do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Oct. 20, 1850 Algernon Merryweather, DS set qr section post Cedar 12 N54W 49
Sugar 14 N10W 23

DEc. 28, 1961 Billy D. Buckler, RLS "Re-established by single proportionate measurement between Section Corner 1/2 mile West and 1/4 corner 2 miles east and in old E and W fence line.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 6, 2000 Thomas P. O'Brien, PS recovered Mich. Dept. of Cons. cap on pipe stamped to identify and verified by distances to corners East and West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Michigan Department of Conservation cap on pipe.

Witnesses:

24" Maple N58°E 88.63'

16" Maple S74°E 85.18'

6" Spruce S41°E 23.90'

3" Spruce S30°W 17.80'

Carsonite Post South 1.0'

Thomas P. O'Brien

Signed by Thomas P. O'Brien

Surveyor's Michigan License No. 21274

Date Dec. 11, 2000



LIBER 4 PAGE: 382