

# SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 10/10/00 TJB

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

FEB 08 2001

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

SECTION

- |                                       |                           |       |
|---------------------------------------|---------------------------|-------|
| 1. Public Land Survey                 | T <u>42N</u> R <u>14W</u> | H3    |
|                                       | T _____ R _____           | _____ |
|                                       | T _____ R _____           | _____ |
|                                       | T _____ R _____           | _____ |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____ |
|                                       | S _____ T _____ R _____   | _____ |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____ |
|                                       | S _____ T _____ R _____   | _____ |

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/391  
JLO Date 12/19/2000 Time 11:53:31

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien, in a field survey on 10/31/00, 10x do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3								X					
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

April 12, 1851 Algernon Marryweather, Ds set 1/4 post Cedar 8 in S28E 16 links  
Tamarack 6 in N27W 4 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct.31, 2000 Thomas P. O'Brien, PS set corner by single proportionate measurement between G3 and I3. Set Schoolcraft County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.

Witnesses:

8" Cedar N36°W 12.43'

4" Cedar S8°W 10.10'

8" Tamarack N43°E 49.11'

3" Cedar S86°E 19.71'


Carsonite Post North 1.0'

Squared Post N83°E 23.2'(FD.)

Signed by Thomas P. O'Brien

Surveyor's Michigan License No. 21274

Date Dec.11, 2000



LIBER 4 PAGE: 391