

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

DATE 10/10/00 *DOB*

**SURVEY &
REMONUMENTATION**

FEB 08 2001

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>14W</u>	<u>I3</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/386
JLV Date 12/19/2000 Time 11:53:28

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 10/30/00 ~~X19X~~ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3									X				
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

April 9, 1851 Algernon Merryweather, DS set section corner, Sections 2,3,10,11
Tamarack 10 in N35E 12 links Spruce 5 in S45W 8 links

June 9, 1976 Herbert L. Fluharty, RLS "set 5/8"x18" iron and cap at original distance from NE cor. in vicinity verified by Don Phillips as told to him by Bill Johnson (deceased) an area resident for 80±years. Phillips lived in area for 20 years. Phillips said that Johnson told him the corner was a glass bottle in centerline road. dug 3'x6'. No glass found, 32'± w. of centerline creek.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct.30, 2000 Thomas P. O'Brien, PS found 5/8"x18" iron and 18223 cap. Reset with Schoolcraft County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.

Witnesses:

- Angle iron culvert post S54°E 31.35'
- Angle iron culvert post N77°E 44.72'
- 6" Tamarack S10°E 65.58'
- 12" Cedar S25°W 47.08'
- Carsonite Post N5°E 30.0'

Thomas P. O'Brien

Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274



Date Dec.11, 2000