

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

**SURVEY &
REMONUMENTATION**

DATE 10/10/00 *TPB*

FEB 08 2001

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Schoolcraft
(County)

Located in:

Corner Code #

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/396
JLV Date 12/19/2000 Time 11:53:34

**SECTION
1P**

- | | | |
|------------------------------------|---------------------------|-------|
| 1. Public Land Survey | T <u>42N</u> R <u>14W</u> | I6 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15	X	14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas P. O'Brien, in a field survey on 11/28/00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

April 9, 1851 Algernon Merryweather, DS set 1/4 post Sugar 10 in S85E 15 links
Sugar 7 in N80W 4 links
May 25, 1950 Carl Christensen observed above original Maple 7", BT with scribe marks and placed 2"x4" long iron pipe with brass cap thereon."
September 26, 1980 Robert E. Schmeling, RLS "Found in place above 2" iron pipe and brass cap and remains of original Maple 7" BT."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov.28, 2000 Thomas P. O'Brien, PS found in place 2" iron pipe and brass cap and bearing tree stump remains. Also found Schmeling bearing trees in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2" iron pipe with brass cap
Witnesses:
10" Beech N59°W 14.9'
12" Maple N54°E 38.8'
10" Beech S23°E 21.6'
12" Beech S73°W 29.3'
All measured to face of blaze.



Signed by Thomas P. O'Brien

Date Dec.11, 2000

Surveyor's Michigan License No. 21274

LIBER 4 PAGE: 396