

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**
DATE 10/10/00 JPB

**SURVEY &
REMONUMENTATION**
FEB 08 2001
SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>14W</u>	<u>K2</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1 LC 4/373
JLO Date 12/19/2000 Time 11:53:19

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2	X		1	
3													
4	7		8		9		10		11			12	
5													
6	10		17		16		15		14			13	
7													
8	19		20		21		22		23			24	
9													
10	30		29		28		27		26			25	
11													
12	31		32		33		34		35			36	
13													

I, Thomas P. O'Brien, in a field survey on 11/6/00, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

April 7, 1851 Algernon Merryweather, DS set 1/4 post Cedar 8 in S65W 4 links
Cedar 7 in N49E 19 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 6, 2000 Thomas P. O'Brien, PS found iron bar with 21274 cap at correct corner position for proportional measurement between K1 and K3. Reset with Schoolcraft County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.

Witnesses:
8" Tamarack S6°W 38.93'
4" Tamarack S72°E 26.15'
10" Tamarack N51°E 27.95'
10" Tamarack N57°W 62.80'
Carsonite Post North 1.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec. 11, 2000