

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**
DATE 10/10/00 JTB

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &
REMONUMENTATION**

FEB 08 2001

For corners in

Schoolcraft
(County)

Located in:

Corner Code #

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1 LC 4/381
JLV Date 12/19/2000 Time 11:53:24

SECTION

1. Public Land Survey

T 42 N R 14 W K3
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas P. O'Brien, in a field survey on 10/17/00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

April 7, 1851 Algernon Merryweather, DS set section corner Sections 1,2,11,12
Sugar 20 in S62W 18 links Sugar 26 in N20E 21 links

June 9, 1976 Herbert L. Fluharty, RLS "fd. nail & tin in centerline road intersection set 5/8" iron & cap."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct.17, 2000 Thomas P. O'Brien, PS found 5/8" iron bar with 18223 cap at centerline road intersection. Reset with 1/2" iron bar with O'BRIEN 21274 cap in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" iron bar with O'BRIEN 21274 cap in monument box.
Witnesses:
Power Pole N60°E 40.0'
Road sign post S32°W 59.53'
Top of Culvert guard post S34°E 64.93'
Carsonite Post N7°E 33.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec.18, 2000