

SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED

SURVEY &  
REMONUMENTATION

FEB 08 2001

SECTION

DATE 10/10/00 JOB LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft (County)	Located In:	Corner Code #
	T <u>42N</u> R <u>14W</u>	<u>K6</u>
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/374  
JLV Date 12/19/2000 Time 11:53:20

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien, in a field survey on 10/17/00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

April 5, 1851 Algernon Merryweather, DS set 1/4 post Birch 8 in South 18 links  
Cedar 7 in North 10 links

March 1984 William F. Bowman, LLS "set by proportionate measure on line between  
K5 and K7.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 17, 2000 Thomas P. O'Brien, Ps found P.K. from 1998-99 corner preservation resurface project. Reset with 1/2" iron bar with OBRIEN 21274 cap in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" iron bar with OBRIEN 21274 cap in monument box.

Witnesses:

6" Cedar N55°W 55.05'

8" Cedar S58°W 56.0'

Power Pole S15°E 91.23'

Carsonite Post S85°E 33.0'

Corner falls in N and S centerline.



Signed by Thomas P. O'Brien  
Surveyor's Michigan License No. 21274

Date Dec. 18, 2000