

FEB 08 2001

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 10/10/00 TDB

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft (County)

Located In:

Corner Code #

SIGRID HEDBERG SCHOOLCRAFT CO. REGISTER 1P Page 1 of 1 LC 4/407 JLV Date 12/19/2000 Time 11:53:41

- 1. Public Land Survey T 42N R 14W K7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Thomas P. O'Brien, in a field survey on 10/17/00, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 and an asterisk in row 7, column K.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

April 5, 1851 Algernon Merryweather, DS set section corner Sections 13,14,23,24 Tamarack 7 in S40W 33 links Cedar 6 in N60E 24 links.

March 1984 William F. Bowman, LLS "set by evidence of road location, old fence lines and corners 1 mile South and 2 miles North."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct.17, 2000 Thomas P. O'Brien, PS found P.K. from 1998-99 corner preservation resurface project. Reset with 1/2" iron bar with OBRIEN 21274 cap in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" iron bar with OBRIEN 21274 cap in monument box.

Witnesses:

- 8" Cedar S62°W 49.0'
6" Cedar N41°W 60.77'
6" Cedar N66°E 61.45'
Power Pole S22°E 82.90'
Centerline East 3.5'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec. 18, 2000

LIBER 4 PAGE: 407