

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED
DATE 10/10/00 TOB**

**SURVEY &
REMONUMENTATION**

FEB 08 2001

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>14W</u>	<u>K10</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/404
JLV Date 12/19/2000 Time 11:53:39

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 10/17/00 ~~X10x~~ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26	*	25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

April 4, 1851 Algernon Merryweather, DS set 1/4 post Spruce 8 in S71E 3 links Balsam 4 in N60W 8 links.

March 1984 William F. Bowman, LLS "set by proportionate measure on line between K9 and K11."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Oct.17, 2000 Thomas P. O'Brien, PS found P.K. from 1998-99 corner preservation resurface project. Reset with 1/2" iron bar with OBRIEN 21274 cap in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" iron bar with OBRIEN 21274 cap in monument box.

Witnesses:

- Power pole S54°E 36.85'
- 16" Cedar N76°W 59.35'
- 18" Tamarack S76°W 86.50'
- Centerline West 2.0'
- Carsonite Post S85°E 40.0'



Signed by Thomas P. O'Brien

Date Dec.18, 2000

Surveyor's Michigan License No. _____