

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

DATE 10/10/00 JOB

**SURVEY &
REMONUMENTATION**

FEB 08 2001

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

Schoolcraft (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>14W</u>	<u>K11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/403
JLV Date 12/19/2000 Time 11:53:39

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 10/17/00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
March 31, 1851 Algernon Merryweather; DS set section corner Sections 25,26,35,36
Birch 10 in N30E 12 links Birch 20 in S80W 5 links

July 17, 1902 Eugene Ford, Co. Surveyor "ironpost set at corner fence due west 32 links."

Nov.1978 Thomas P. O'Brien, RLS "found R.R. spike in intersection of N&S and E&W roads."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct.17, 2000 Thomas P. O'Brien, PS found P.K. from 1998-99 corner preservation resurface project. Reset with 1/2" iron bar with OBRIEN 21274 cap in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" iron bar with OBRIEN 21274 cap in monument box.


Witnesses:

Power Pole N55°E 39.60'

Power Pole S45°E 45.20'

Power Pole S50°W 46.20'

Carsonite post N85°W 40.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec.18, 2000