

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

DATE 10/10/00 JOB

**SURVEY &
REMONUMENTATION**

FEB 08 2001

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 14W	L1 ✓
	T 43N R 14W	L13
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/368
JLV Date 12/19/2000 Time 11:53:16

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas P. O'Brien, in a field survey on 11/10/00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Oct. 20, 1850 Algernon Morryweather, DS set 1/4 post Maple 20 N53E 17 Birch 18 N63W 7.

Dec. 28, 1961 Billy D. Buckler, RLS " corner was replaced from wood post which seems to check well with corners in vicinity. No original evidence."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 10, 2000 Thomas P. O'Brien, PS recovered Moch. Dept. of Cons. cap on pipe stamped to identify and verified by distance to West and existing Buckler BT's.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Michigan Department of Conservation cap on pipe.

Witnesses:

- 12" Maple N41°E 16.38' -Buckler BT
- 14" Maple N21°W 31.87'
- 20" Maple S68°W 24.74' -Buckler BT
- 12" Maple S28°E 33.85'
- Carsonite Post North 1.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec. 11, 2000