

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

**SURVEY &
REMONUMENTATION**

DATE 10/10/00 JOB

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 08 2001

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

SIGRID HEDBERG

SCHOOLCRAFT CO. REGISTER

SECTION 1P

Page 1 of 1

LC 4/419

JLO Date 12/28/2000

Time 11:28:13

- | | | |
|------------------------------------|---------------------------|-----------|
| 1. Public Land Survey | T <u>42N</u> R <u>14W</u> | <u>M3</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 10/17/00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													X
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

April 1851 Algernon Merryweather, DS set Corner 1 & 12 Sugar 28 in N47W 21 links Balsam 10 " S49W 23 "

March 1984 William F. Bowman, LLS "set by evidence of road location and corners one mile east and west."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 17, 2000 Thomas P. O'Brien, PS: found 1" pipe with 4" Mead cap and LS 28406 stamp as set by Bowman.'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" pipe with 4" Mead cap stamped to identify.

Witnesses:

10" Tamarack S44°E 19.33'

4" Tamarack S21°W 20.82'

Apple Clump S75°W 17.50'

Carsonite Post North 1.0'



Thomas P. O'Brien

Signed by Thomas P. O'Brien

Date Dec. 19, 2000

Surveyor's Michigan License No. 21274

LIBER 4 PAGE: 419