

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

**SURVEY &
REMONUMENTATION**

FEB 08 2001

DATE 10/10/00 TPB

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T42N R14W	M4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1 LC 4/421
JLO Date 12/28/2000 Time 11:28:14

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 11/10/00, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	X
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

April 1851 Algernon Merryweather, DS set 1/4 post Cedar 12 in N60W 18 links
Cedar 14 in S85W 20 links.

March 1984 William F. Bowman, LLS "set by proportionate measure on line between M3 and M5."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 10, 2000 Thomas P. O'Brien, PS found 1" pipe with 4" Mead cap and LS 28406 stamp as set by Bowman."

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" pipe with 4" Mead cap stamped to identify.

Witnesses:

- 4" Spruce N26°E 20.18'
- 4" Spruce N54°W 10.25'
- 10" Cedar N45°E 38.20'
- 10" Cedar N85°W 35.70'
- Carsonite Post North 1.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec. 19, 2000