

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

DATE 10/10/00 JOB

**SURVEY &  
REMONUMENTATION**

FEB 08 2001

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>14W</u>	M6
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/427  
JLV Date 12/28/2000 Time 11:28:18

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

I, Thomas P. O'Brien, in a field survey on 11/10/00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

April 1851 Algernon Merryweather, DS set 1/4 post Balsam 6 in N65W 10 links  
Balsam 5 in S55W 14 links.

March 1984 William F. Bowman, LLS " set by proportionate measure on line between M5 and A7 (42-13).

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Nov.10, 2000 Thomas P. O'Brien, PS found 1" pipe with 4" Mead cap and LS 28406 stamp as set by Bowman.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1" pipe with 4" Mead cap stamped to identify.

Witnesses:

- 6" Balsam S26°W 10.03'
- 8" Cedar S58°W 28.90'
- 8" Cedar N83°W 19.02'
- 8" Cedar N35°W 43.30'
- Carsonite Post North 1.0'



Signed by Thomas P. O'Brien  
Surveyor's Michigan License No. 21274

Date Dec.19, 2000

LIBER 4 PAGE: 427