

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

DATE 10/10/00 DOB

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &  
REMONUMENTATION**

FEB 08 2001

SECTION

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42NR14W</u>	<u>M8</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/417  
JLV Date 12/28/2000 Time 11:28:11

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien, in a field survey on 11/27/00, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

April 1851 Algernon Merryweather set 1/4 post B Ash 10 in S40W 16 links Cedar 8 " N8W 12".

March 1984 William F. Bowman LLS "set by proportionate measure on line between M7 and M9."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 27, 2000 Thomas P. O'Brien found 1" pipe with 4" Mead cap and LS 28406 stamp as set by Bowman.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" pipe with 4" Mead cap stamped to identify.

Witnesses:

8" Cedar S71°W 21.20'

6" Cedar N39°E 9.35'

12" Cedar S19°E 14.10'

8" Cedar N52°W 13.0'

Carsonite PPost North 1.0'



Signed by Thomas P. O'Brien

Date Dec. 27, 2000

Surveyor's Michigan License No. 21274

LIBER 4 PAGE: 417