

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

**SURVEY &
REMONUMENTATION**

FEB 08 2001

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey

T 42N R 14W

M10

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1 LC 4/414
JLV Date 12/28/2000 Time 11:28:10

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 10/31/00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		X
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

April 1851 Algernon Merryweather DS set 1/4 post Maple 3 in Corner Post Balsam 6 in S30W 22 links.

March 1984 William F. Bowman LLS "set by proportionate measure on line between M11 and A10 (42-13).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct.31, 2000 Thomas P. O'Brien PS found 5/8" rebar with 28406 cap in N and S centerline of County Road. Reset with Schoolcraft County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.

Witnesses:

- Telephone Pole N85°W 25.0'
- 12" Cedar S66°E 39.95'
- 10" Y. Birch S59°W 60.86'
- 8" Cedar N70°W 48.70'
- Carsonite Post N85°W 25.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec. 27, 2000