

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 43/42 N.R. 15 & 16 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Town corner for T43N R16W 36/31 T43N R15W  
T42N R15W 1/6

CORNER MONUMENT 1" Iron pipe with 4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8/10/67, Frank J. Bray with M. Burnis

WITNESSES TO CORNER..... 18" R. Pine (S6)(NBT) S 85° E, 166 Links



16" R. Pine (S1)(NBT) S 20° W, 186 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Reestablished by double proportioned measurement between 1/4 corners 1 1/2 miles to west and 2 1/2 miles to east and between section corners 1 mile to north and to south. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 10/16/67  
Frank J. Bray  
REGISTERED LAND SURVEYOR