

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42-43 N.R. 15 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sec. 4 and Sec. 33.

CORNER MONUMENT 2" I.D. iron pipe with 2 1/2" brass cap stamped "33-1/4-4, c.c."

DATE MONUMENT PLACED AND WITNESSED Date placed unknown; re-witnessed 5/21/64

WITNESSES TO CORNER..... Jack Pine 7 N 22 1/2 W 96 1/2 links, "1/4 s, NBT"



White Pine 4 S 65 W 82 links, "1/4 s, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Pipe set by Carl Christensen, presumably from original bearing trees or personal knowledge of corner's history. Road construction has destroyed any evidence of BT's. Corner seems to check well with natural features and other corners eastward along the township line.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger RLS 13581 DATE 9/7/65

Billy D. Buckler RLS 8887
REGISTERED LAND SURVEYOR

4/13/72

Billy D. Buckler