

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42-43 N.R. 15W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 2-3-34-35

CORNER MONUMENT 1" Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 5-22-61

WITNESSES TO CORNER..... 12" Cedar (S35 NBT) N53°E 48 links



10" Cedar (S2 NBT) S80°E 26 links

7" Cedar (S3 NBT) S76°W 16 links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by single proportionate measure from Corners $\frac{1}{2}$ mile East and $1\frac{1}{2}$ miles West.
Found Cruisers' register tree facing Corner. No positive evidence of original corner.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR
Billy D. Buckler

DATE December 28, 1961