

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 42-43 N.R. 15 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 2 and 35

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 5/11/61 with Duaine St. Ours.

WITNESSES TO CORNER... 18" Red Pine (1/4S NBT) S 42 deg. W. 45 Links



9" Jack Pine (1/4 S NBT) S 58 deg. E 16 Links

5" J. Pine (1/4S NBT) N 25 deg. W 06 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one W. Pine B.T. bearing N 49 deg. E, 61 Links, which is laying down, badly burned. Faces are on the lower side of the log in excellent condition. Corner found while checking lines ran by District personnel.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 9/15/61  
REGISTERED LAND SURVEYOR  
Billy D. Buckler