

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Schoolcraft COUNTY  
T 42 N R 15 W

DESCRIPTION OF CORNER 1/4 for sections  $\frac{15}{22}$

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 7/22/69, F. J. Bray with M. Burnis

WITNESSES TO CORNER..... 8" Balsam (1/4 S) (NBT) N 57° W, 15 links



8" W. Birch (1/4 S) (NBT) S 11° E, 31 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from original BT (W. Pine 14" N 07° E, 20 links).  
Now a burned stump with notch and portion of scribe marks on lower face.  
Rotted Hemlock wood in place for other BT. Corner found by Forester Wallace  
and Forestry Aide Burnis.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray  
REGISTERED LAND SURVEYOR

DATE

8/15/69

Frank J. Bray

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68