

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

SCHOOLCRAFT CO.

3 CORNERS

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>42</u> N. XX R. <u>15</u> W.	
2. PROPERTY CONTROLLING IN SECTION <u>30</u>	T. <u>42</u> N. XX R. <u>15</u> W.	<u>13, 14, 16</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ R. _____ E. _____ S. _____ R. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12-21, 1988, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 13 S.E. 1/16 Corner of Section 30. *Not previously set.*
- 14 South 1/16 Corner of Section 30. *Not previously set.*
- 16 East 1/16 Corner of Section 30. *Not previously set.*

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 13 Corner set at center of S.E. 1/4 of Section 30.
- 14 Corner set midpoint on line between S.E. Corner and East 1/4 Corner of Section 30.
- 16 Corner set midpoint on line between S.E. Corner and South 1/4 Corner of Section 30. Found a squared and scribed post 1.02' S.W. of this location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
DNR Monument set at all three corners.

- | | | |
|-----------------------------|----------------------------|---------------------------|
| 13 12" Cedar, N28°W, 25.7' | 14 6" Cedar, N25°W, 9.9' | 16 12" Maple, S60°E, 5.8' |
| 12" Cedar, N13°E, 25.2' | 8" Cedar, N16°E, 21.95' | 14" Maple, N70°E, 27.9' |
| 6" Cedar, N58°E, 26.8" | 8" Cedar, N80°E, 8.95' | 10" Maple, S79°W, 45.6' |
| 8" Cedar, S38°E, 15.7' | 6" Cedar, S45°E, 28.3' | 8" Maple, N31°W, 12.7' |
| 1 1/2" Pipe, S75°W, 155.08' | 1 1/2" Pipe, N86°W, 71.62' | |

SIGNED BY Gerald L. Wiggins DATE 2-14-89


SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET