

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

SCHOOLCRAFT CO.

2 CORNERS

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. <u>15</u> W.	C-12, B-13
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-29, 1989, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C-12 East 1/4 Corner of Section 31. OBT'S: Cedar 12", N55°W, 25 lks, & Birch 12, S35°E, 17 lks.

B-13 South 1/4 Corner of Section 31. OBT'S: Hemlock 32", N42°E, 19 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-12 Corner set midpoint on line between N.E. Corner and S.E. Corner of Section 31.

B-13 Corner set record distance and bearing from remains of large Hemlock stump. This position fits original river calls and fits single proportionate measure between original S.W. Cor. and original S.E. Cor. of Section 31.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


DNR Monument set at both corners.

C-12 4" Cedar, S29°E, 21.6'
8" Cedar, N52°E, 24.3'
8" Cedar, N11°E, 32.4'
6" Cedar, N55°W, 5.25'

B-13 8" Cedar, S48°E, 12.3'
8" Cedar, N58°E, 12.2'
8" Cedar, N09°W, 27.4'
5" Cedar, N40°W, 14.0'

SIGNED BY Gerald L. Wiggins
SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

DATE 2-14-89



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____
CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET