

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

SCHOOLCRAFT CO.

4 CORNERS (SEE BACK).

| FOR CORNERS OF -- | LOCATED IN -- | CORNER CODE NUMBER | |
|---------------------------------------|---|--------------------|--|
| 1. PUBLIC LAND SURVEY | T. <u>42</u> N. R. <u>15</u> W. | B-11 | REGISTER OF DEEDS STAMP AND FILING NUMBER |
| 2. PROPERTY CONTROLLING IN SECTION | <u>31</u> , T. <u>42</u> N. R. <u>15</u> W. | 5 | |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. _____ N. S. R. _____ E. W. | | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | | |
| 5. PRIVATE CLAIMS _____ | | | |

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1-11 & 2-1, 1989, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B-11 North 1/4 Corner of Section 31. Carl Christianson corner found by Billy D. Buckler R.L.S. and witnessed on 1-8-57.
- 5 North 1/16 Corner of Section 31. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-11 Re-witness Buckler's record, dated 1-11-57 which was a re-witness of a pipe by Carl Christianson placed from an OBT, Cedar 10, N58°W, 13 links still alive.
- 5 Corner set M.P.O.L. between North 1/4 Corner and the computed Center Corner of Section 31 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-11 Christianson 2" pipe with 2 1/2" Brass Cap, 5 DNR Monument

Buckler's 8" Cedar, N85°E, 15.8'
Buckler's 8" Cedar, N27°E, 20.5'
OBT Green 20" Cedar, N58°W, 8.6'

6" Cedar, S47°W, 35.6'
6" Cedar, N80°W, 33.5'
6" Cedar, N53°W, 6.25'
5" Cedar, N50°E, 8.25'

8" Cedar, S4°E, 13.1'
5" Cedar, West, 11.8"

SIGNED BY Gerald L. Wiggins DATE 2-14-89


SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET