

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

SCHOOLCRAFT  
(County)

Located in:

Corner Code ##

1. Public Land Survey	T	42N	R	15W	E-2
	T	42N	R	15W	E-3
	T	42N	R	15W	E-4
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Gerald L. Wiggins in a field survey on 6-25, 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

- E-2 1/4 Corner between 5 and 4. OBT'S: Balsam 12, S17°W, 10 lks. & Balsam 12, N42°E, 33 lks.  
 E-3 Section corner 5,4, 8,9. OBT'S: Sugar 10" N32°E, 14 lks. & Sugar 8, S35° W, 31 lks.  
 E-4 1/4 Corner between 8 and 9. OBT'S: Birch 6, S44°W, 5 lks. & Cherry 7, N49°E, 15 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-2 Corner set midpoint on line between corners 1/2 mile north and south.  
 E-3 Corner set by double proportionate measure between corners 2 miles West and original corner 1 mile east, a corner 1 mile North and a 1/4 corner 1/2 mile south.  
 E-4 Corner set at found fence iron, distance south to river checks o.k.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**DNR MONUMENTS PLACED AT ALL THREE CORNERS.**

E-2	8" Maple, S87°W, 11.1'	E-3	16" Maple, S14°E, 12.4'	E-4	12" R.Pine, S6°W, 98.0'
	12" Maple, N82°E, 11.65'		10" Maple, S14°W, 15.3'		12" Maple, North, 12.25'
	10" Maple, S71°E, 4.4'		16" Beech, N44°W, 15.9'		10" Spruce, N25°E, 27.2'
	8" Maple, S15°E, 13.55'		5" Maple, N67°E, 11.7'		12" Spruce, N56°E, 57.1'

Signed by

*Gerald L. Wiggins*  
 Gerald L. Wiggins

Surveyor's Michigan License No.

23521

Date

6-26-91

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS

