

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 21 T 42N R 15W	10
	S _____ T _____ R _____	(GCDB 300320)
	S 21 T 42N R 15W	11
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	(GCDB 320320)
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on 08/03/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(10-Sec. 21) South 1/16 corner between Sections 20 and 21.
 Not previously monumented.

(11-Sec. 21) Southwest 1/16 corner, Section 21.
 Not previously monumented.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(10-Sec. 21) Established the position for the corner midway and on the Section line between Section corner 1322.24' south and Quarter corner 1322.24' north.

(11-Sec. 21) Established the position for the corner at the intersection of straight lines connecting opposite 1/16 corners, those to the west and south being monumented.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(10) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 5" Tamarack N18°W 9.38' mrkd "S1/16 BT"
 6" Tamarack S28°W 5.80' do
 7" Tamarack S80°E 13.30' do
 5" Tamarack N48°E 8.92' do
 E= 8061996.185 N= 137316.884

(11) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 5" Balsam S37°E 16.60' mrkd "SW1/16 BT"
 14" Cedar S26°W 22.41' do
 10" Cedar S66°W 15.20' do
 8" Balsam N15°E 2.66' do
 E= 8062397.879 N= 137322.883

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum.
 Coord. Ref.=NGS PID DL6164: N= 131822.939 m. E= 8059239.498 m.

Signed by Stephan J. Szyszkoski Date 11/16/2015
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Resources Division