

OCT 26 1995

COMMISSION

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

DATE March 10, 1995 LAND CORNER RECORDATION CERTIFICATE

For corners in 00B Filing Requirement of Act 74, Mich. P.A. 1970

Schoolcraft <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 42N R 15W T 42N R 16W	A-6 A-7 M-6 M-7
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

Received & Filed this 5 day of
September 19 95 at 11:12 AM
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	16	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

Thomas P. O'Brien in a field survey on Dec. 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-6 (West 1/4 Corner Sec. 18)
Aug. 3, 1845 John Burt, D.S. set gr. section post.
W. Pine 30 N71W 20 Fir 6 S61W 22

A-7 (N.W. Corner Sec. 19)
Aug. 3, 1845 John Burt, D.S. set post corner.
Tamarack 5 N24W 66 do 5 N65W 93

Sept. 23/50 Algernon Merryweather, D.S. corner 18&19 West Boundary
Tamarack 7 N60E 1.23 do 6 S43E 1.11

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 No evidence of the original corner remains reestablished the corner by single proportionate measurement between corners A-5 & A-7.

A-7 Found iron pipe set by Carl Christensen from original bearing tree "Tamarack 7" N60E 123 links" as noted in County Surveyors Book.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 Schoolcraft County monument stamped to identify
4" Beech N24°W 7.75'
12" Hemlock EAST 13.98'
5" Maple S40°W 4.76'
Post WEST 1.5'

A-7 2" iron pipe w/2 1/2" brass cap stamped "C.C."

16" Tamarack N86E 95.3'
12" Tamarack N32E 163.4'
12" Tamarack N9W 135.0.

13 | 18
24 | 19



Signed by Thomas P. O'Brien Date March 10, 1995

Surveyor's Michigan License No. 21274