

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

DATE 12/10/96

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

MAY 16 1997

COMMISSION

For corners in

Schoolcraft  
(County)

Located In:

Corner Code #

- |                                    |                            |               |
|------------------------------------|----------------------------|---------------|
| 1. Public Land Survey              | T <u>42</u> NR <u>15</u> W | <u>A-12</u> ✓ |
|                                    | T <u>42</u> NR <u>16</u> W | M-12          |
|                                    | T ___ R ___                | _____         |
|                                    | T ___ R ___                | _____         |
| 2. Property Controlling in Section | S ___ T ___ R ___          | _____         |
|                                    | S ___ T ___ R ___          | _____         |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___          | _____         |
|                                    | S ___ T ___ R ___          | _____         |

Received & Filed this 30 day of  
Dec 1996 at 9:33 AM

Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien in a field survey on Oct. 25, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-12 Aug. 3, 1845 - John Burt D.S. set qr. section post.  
W. Birch 5 N86W 21 links do. 5 S44W 27 "

March 14 & 15, 1988 - Gerald L. Wiggins L.S. set corner " midpoint on line between N.E. Corner and S.E. Corner of section."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12 Oct. 25, 1996 - Thomas P. O'Brien, P.S. recovered corner as set by Gerald L. Wiggins. Corner distances check well for single proportionate measurement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12 D.N.R. monument found.

Witnesses: Fd. 8" Cedar - West - 20.95'  
Fd. 10" Cedar - N51°W - 29.00'  
NBT. 6" Cedar - N28°E - 16.90'  
Fd. 6" Cedar - S39°E - 18.05'



*Thomas P. O'Brien*

Signed by Thomas P. O'Brien

Date Dec. 26, 1996

Surveyor's Michigan License No. 21274