

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

RECORDS & DOCUMENTATION

JAN 30 1996

COMMISSION

DATE Dec. 7, 1995 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft _____ Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey
 T 42N R 15W A13 ✓
 T 42N R 16W MI3
 T 41N R 15W AL
 T 41N R 16W MI

2. Property Controlling S _____ J _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Received & Filed this 26 day of
Dec. 1995 at 2:30 PM
 Sigrid I. Hedberg
 Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas P.O'Brien, in a field survey on Dec. 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 A13 (S.W. Corner Sec. 31)
 "post corner of towns 41 & 42N between ranges 15 & 16 W
 W.Pine 18 S42W 46 Aspen 7 N53E 44"
 August 6, 1845
 John Burt D.S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 A13 Dec. 6, 1995 Thomas P.O'Brien, PS recovered pipe w/ 4" aluminum disc stamped "Michigan Department of Conservation - State Forest" stamped to identify. Found white pine stump S42W 46 lks. Corner has been monumented 20+ years.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A13 Pipe w/4" aluminum cap stamped to identify
 Witnesses:
 12" White Birch N17°W 9.47'
 12" Maple N39°E 56.0'
 12" Maple S70°E 28.25'
 12" Hemlock South 33.37'
 Cedar Post North 1.5'



Signed by Thomas P.O'Brien Date Dec. 20, 1995

Surveyor's Michigan License No. 21274