

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

**DATE** Dec. 7, 1995 **LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 30 1996

COMMISSION

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>15W</u>	<u>B11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Received & Filed this 28 day of  
Dec. 1995 at 2:49 PM  
Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Thomas P. O'Brien, in a field survey on Sept. 26, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

B11 (1/4 Section corner common to Sections 30 & 31)  
Sept. 21, 1850 Algernon Merryweather, D.S. set qr. section post.  
Cedar 30 in West 25 links Cedar 18" S38W 30"  
Jan. 8, 1957 Billy D. Buckler, RLS recovered 2" pipe w/2 1/2" brass cap set by Carl Christianson, Manistique, S58°E 13 links from original bearing tree.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B11 Sept. 26, 1995 Thomas P. O'Brien, PS recovered 2" pipe w/2 1/2" brass cap set by Carl Christianson and recorded by Billy D. Buckler, RLS in Liber 3 Page 414 Schoolcraft County Register of Deeds. Original bearing tree N58°W 13 links still living in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B11 2" pipe w/2 1/2" brass cap stamped to identify.  
Witnesses:  
8" cedar N85°E 15.80'  
8" Cedar N27°E 20.50'  
20" Cedar N58°W 8.58' (Original bearing tree)  
8" Cedar S4°E 13.10'  
5" Cedar West 11.80'  
Cedar Post North 1.0'



Signed by Thomas P. O'Brien Date Dec. 27, 1995  
Surveyor's Michigan License No. 21274