

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

SURVEY &  
REMONUMENTATION

DATE 11/8/96 <sup>JOE</sup> LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MAY 16 1997

COMMISSION

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42NR15W</u>	<u>C-3</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Received & Filed this 16 day of  
December 19 96 at 11:58 AM  
Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien in a field survey on Nov. 12, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3			X										
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-3 (N.E. Corner Section 7)  
Sept. 26, 1850 - Algernon Merryweather D.S. set corner post.  
Hemlock 20 in. S57E 39 links do. 18 in. N54W 60 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-3 Nov. 12, 1996 - Thomas P. O'Brien, P.S. re-established corner by double proportionate measurement. No evidence of G.L.O. survey or subsequent restoration recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-3 Schoolcraft County Monument stamped to identify.

Witnesses: 10" Red Pine - N61°W - 38.31'  
10" Red Pine - N24°W - 35.68'  
6" Red pine - S12°W - 112.41'  
8" Red Pine - S65°W - 181.50'  
4" Cedar Post - South - 2.0'



Thomas P. O'Brien  
Signed by Thomas P. O'Brien

Date Nov. 19, 1996

Surveyor's Michigan License No. 21274