

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

DATE 11/18/96 <sup>JOB</sup>

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
RECORDATION  
MAY 16 1997  
COMMISSION

For corners in

Schoolcraft  
(County)

Located In:

Corner Code #

- |                                    |       |                 |            |
|------------------------------------|-------|-----------------|------------|
| 1. Public Land Survey              |       | <u>T42NR15W</u> | <u>C-5</u> |
|                                    |       | T ___ R ___     | _____      |
|                                    |       | T ___ R ___     | _____      |
|                                    |       | T ___ R ___     | _____      |
| 2. Property Controlling in Section | S ___ | T ___ R ___     | _____      |
|                                    | S ___ | T ___ R ___     | _____      |
| 3. Miscellaneous Property in Sec.  | S ___ | T ___ R ___     | _____      |
|                                    | S ___ | T ___ R ___     | _____      |

Received & Filed this 16 day of  
December 19 96 at 12:00 P.M.  
Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5			X										
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas P. O'Brien, in a field survey on Nov. 13 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 0-5 (N.E. Corner Sec. 18)  
Sept. 27, 1850 Algernon Merryweather D.S. set corner post.  
Cedar 8 in. N46W 27 links Hemlock 7 in. S65E 22"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 5 Nov. 13, 1996 - Thomas P. O'Brien P.S. re-established corner by double proportionate measurement. No evidence of G.L.O. survey or subsequent restoration recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 5 Schoolcraft County Monument stamped to identify.

- Witnesses:
- 8" Spruce - N11°E - 23.48'
  - 10" Cedar - S71°E - 52.75'
  - 4" W. Pine - S78°W - 27.77'
  - 4" Tamarack - N76°W - 48.94'
  - 4" Cedar Post - North - 3.0'



*Thomas P. O'Brien*

Witnessed by Thomas P. O'Brien

Surveyor's Michigan License No. 21274

Date Nov. 19, 1996