

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

DATE May 12, 1995 **LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 30 1996
COMMISSION

For corners in

Schoolcraft <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 42 NR 15 W T 42 NR 15 W T _____ R _____ T _____ R _____	C-11 C-12 ✓
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Received & Filed this 6th day of
December 19 95 at 11:35 AM
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

I, Thomas P. O'Brien in a field survey on Nov. 7, 1995
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11		X										
12	31	X	32	33	34	35	36					
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-11 (Section Corner common to sections 29,30,31,32)
Sept. 19, 1850 Algernon Merryweather D.S. set corner post.
Hemlock 12 in. N81E 44 links Hemlock 8" S20W 14"
- C-12 (East 1/4 Corner of Sec. 31)
Sept. 19, 1850 Algernon Merryweather D.S. set qr. section post.
Cedar 12 in. N55W 25 links Birch 12" S35E 17"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-11 Jan. 8, 1957 Billy D. Buckler, RLS recovered iron pipe with brass cap as set by Carl Christensen, and rewitnessed corner.
Oct. 19, 1994 Thomas P. O'Brien, PS recovered iron pipe w/brass cap set by Carl Christensen from original bearing tree "Hemlock 12" N81E 44 links" as noted in County Surveyors book.
- C-12 Feb. 14, 1989 Gerald L. Wiggins, RLS set 1" pipe with 4" aluminum DNR cap, "midpoint on line between N.E. corner and S.E. corner section 31.
Oct. 19, 1994 Thomas P. O'Brien, PS recovered 1' pipe w/ 4" aluminum DNR cap as set by Gerald L. Wiggins, RLS. Corner had been disturbed - reset from witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-11 2" pipe w/2 1/2" brass cap stamped to identify by "CC".
Witnesses:
14" Hemlock N65°W 33.65' 14" Yellow Birch S41°W 42.85'
6" Cedar S60°E 23.43' 10" Cedar N65°E 25.68' Cedar Post North 2.0'
- C-12 1" pipe w/4" aluminum cap stamped to identify.
Witnesses as established by G. Wiggins L2, P223 in good condition.
4" Cedar S29°E 21.6' 8" Cedar N52°E 24.3'
8" Cedar N11°E 32.4' 6" Cedar N55°W 5.25' Post East 1.5'

Signed by Thomas P. O'Brien, PS

Date Dec. 4, 1995

Surveyor's Michigan License No. 21274

LIBER 4 PAGE: 1

