

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

SURVEY &
REMONUMENTATION

OCT 26 1995

DATE March 10, 1995 008 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
Schoolcraft
(County)

Located In: Corner Code #

1. Public Land Survey	T 42N R 15W	E2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Received & Filed this 10 day of
March 1995 at 2:37 p M
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on January 18, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E2) Quarter corner common to Sections 4-5. Corner established in 1850 by Algernon Merryweather: South corrected between Sec 4 & 5, 40.37 1/4 post, Balsam 12 S17W 10, Balsam 12 N42E 33. Corner filed in 1991 by Gerald L. Wiggins, RLS #23521 as follows: Corner set midpoint on line between corners 1/2 mile north and south. Placed DNR monument. 8" Maple S87W 11.1', 12" Maple N82E 11.65', 10" Maple S71E 4.4', 8" Maple S15E 13.55'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E2) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Recovered the 1991 monument, as described, in good condition, at record bearing and distance from the 1991 accessories. Determined that the 1991 corner position is erroneous pursuant to the Jan. 18, 1995 remonumentation by the undersigned of the corner E3, and by the 1994 discovery of an error in the calculation of an angle, which was used to lay out the 1991 position from nearby survey traverse stations. I reestablished the corner on a straight line between monumented Section corners 2659.68' North and 2635.31' South, being proportionate to the original record. At the position for the corner I placed the 1991 monument, a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum Michigan Department of Natural Resources tablet, appropriately stamped. I defaced the 1991 accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E2) Set a 1" I.D. iron pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails with Ref. tags in:
10" Maple S29E 10.1' "1/4S N8T"
10" Maple N30E 6.6' "1/4S N8T"
8" Maple N34W 8.35' "1/4S N8T"
10" Maple N78W 24.25' "1/4S N8T"
A squared wood post with Schoolcraft County Survey poster affixed is adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 2-28-95
Surveyor's Michigan License No. 33986

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

For the Michigan Department of Natural Resources - Forest Management Division.