

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

RECORDED
JAN 30 1995
COMMISSION

DATE May 12, 1995 **LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft (County)	Located In:	Corner Code -#
1. Public Land Survey	T <u>42 N</u> R <u>15 W</u>	<u>E-4</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Received & Filed this 6 day of
Dec. 1995 at 11:41 A M
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Thomas P. O'Brien, in a field survey on Oct. 17, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-4 (East 1/4 Corner of Sec. 8)
Sept. 26, 1850 Algernon Merryweather D.S. set qr. section post.
Birch 6 in. S44W 5 links Cherry 7 " N49E 15 "

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4 June 25, 1991 Gerald Wiggins, RLS set 1" pipe with 4" aluminum DNR cap " at found fence iron, distance south to river checks well."

Oct. 17, 1994 Thomas P.O'Brien, PS recovered 1" pipe w/4" aluminum DNR cap as set by Gerald Wiggins, RLS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4 1" pipe w/ 4" aluminum cap stamped to identify.

Witnesses:
12" R.Pine S6°W 98.0'
12" Maple North 12.25'
10" Spruce N25°E 27.20'
12" Spruce N56°E 57.10'



Signed by Thomas P. O'Brien, PS Date Dec. 4, 1995

Surveyor's Michigan License No. 21274