

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

DATE Dec. 7, 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

JAN 30 1996

COMMISSION

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>15W</u>	<u>E11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Received & Filed this 21 day of
Dec. 1995 at 2:35 PM
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

I, Thomas P.O'Brien in a field survey on Oct. 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
E11 (Section corner common to Sections 28, 29, 32 & 33)
Sept. 19, 1850 Algernon Merryweather D.S. set corner post.
Balsam 9 in. S33W 21 links Sugar 20" n54E 49 "

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E11 June, 1977 Beryl M. Jones, RLS "found nail in centerline, No witness" reset w/RR spike. Recorded corner in Liber 1 page 229 Schoolcraft County Register of Deeds.
Oct. 18, 1994 Thomas P.O'Brien, PS recovered RR spike as set by Beryl M. Jones. Reset RR spike with iron bar w/21274 cap in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E11 Iron bar w/21274 cap in monument box.
Witnesses:
14" Red Pine N9°W 108.90'
8" Spruce S2°E 54.57'
Power Pole S35°W 32.20'
Cedar Post North 24.50'



Signed by Thomas P.O'Brien Date Dec. 20, 1995

Surveyor's Michigan License No. 21274