

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

LAND CORNER RECORDATION CERTIFICATE

DATE Dec. 7, 1995 **Filing Requirement of Act 74, Mich. P.A. 1977**

For corners in
Schoolcraft
(County)

Located In: _____ Corner Code # _____

- | | | | | | |
|------------------------------------|---|-------|---|-------|-------|
| 1. Public Land Survey | T | 42N | R | 15W | G1 ✓ |
| | T | 43N | R | 15W | G13 |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

CONFIRMED
 MONUMENTATION

FEB 22 1996
 COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas P.O'Brien, in a field survey on Aug. 14, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

May 30, 1841 William A. Burt, D.S. "Set post corner of sections 33&34 Birch 20 N67E 31 Spruce N16W 21
 Sept. 18, 1850 Algernon Merryweather, D.S. "Corner 3&4 north boundary Birch 12 in S15E 22 links Birch 10" S36W 58"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec. 28, 1961 Billy D. Buckler, RLS "re-established corner by single proportionate measure along Township line." Corner recorded in Liber 3, page 413 of Schoolcraft County Register of Deeds.

Aug. 14, 1995 Thomas P.O'Brien, PS recovered pipe w/DNR cap set by Buckler and verified by recorded witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2" pipe w/DNR cap stamped to identify
 Witnesses:
 12" Cedar N33°E 33 1/2 links (Buckler witness)
 8" Cedar S63°E 8 links (Buckler witness)
 16" Hemlock N72°W 32 links (Buckler witness-down stump remains)
 10" Maple S45°W 63.40'
 8" Maple S16°W 7.75'

Thomas P.O'Brien

Signed by Thomas P.O'Brien Date _____

Surveyor's Michigan License No. 21274

