

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

JAN 30 1996

DATE Dec. 7, 1995 LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>15w</u>	<u>G7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	J _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received & Filed this 28 day of
Dec 1995 at 2:47 P M
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7							*						
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas P.O'Brien, in a field survey on Dec.13, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G7 (Corner of Sections 15,16,21 &22)
Sept 18, 1850 Algernon Merryweather, DS
"Section Corner Section 15,16,21,22
Hemlock 12 in S70E 30 links
Do 24in N19W 29 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G7 December 13, 1993 Thomas P.O'Brien, PS recovered a wood post set by persons unknown at corner position. Measurements to 1/4 corner of Sections 15 & 22 is 4' short of GLO distance. Accepted wood post as best evidence of original corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G7 Schoolcraft County monument stamped to identify.
Witnesses:
10" Maple N10°E 42.40'
8" Maple S75°E 36.46'
8" Maple S48°W 17.07'
12" Maple N55°W 96.32'
Cedar Post North 1.5'



Signed by Thomas P.O'Brien Date Dec.27, 1995

Surveyor's Michigan License No. 21274

LIBER 4 PAGE: 29