

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

**DATE** 7/12/96 <sup>0015</sup> **LAND CORNER RECORDATION CERTIFICATE**

**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Schoolcraft</u> <small>(County)</small>	Located In:	Corner Code <u>##</u>
1. Public Land Survey	T <u>42N</u> R <u>15W</u>	<u>G-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Received & Filed this 8th day of  
October 1996 at 11:28 A M  
Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

Thomas P. O'Brien in a field survey on August 15, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G-8 ( $\frac{1}{2}$  Corner common to Sections 21&22)  
Sept. 18, 1850 Algernon Merryweather, D.S. set gr. section post.  
Beech 7 in. S44E 41 links Beech 6 " N36W 25 "

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 August 15, 1996 Thomas P. O'Brien P.S. re-established corner by single proportionate measurement between G-7 and G-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 Set 18" Iron Bar with ID cap in monument box.

Witnesses: Fd. Fence Post - S35°E - 47.33'  
Fd. 14" Maple - N79°W - 38.70'  
M.B.T. Pole - S29°W - 81.15'  
Power Pole - N31°E - 69.05'  
4' Cedar Post - East - 25.0'

SURVEY &  
REMONUMENTATION

DEC 1 6 1996

COMMISSION



*Thomas P. O'Brien*

Signed by Thomas P. O'Brien Date August 15, 1996

Surveyor's Michigan License No. 21274

LIBER 4 PAGE: 45

Handwritten notes at top right.

10/8/1996

0015