

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

DATE May 12, 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 30 1996

COMMISSION

For corners in

Schoolcraft
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 42 N R 15 W
T 41 N R 15 W
T _____ R _____
J _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

G-13 ✓
G-1

Received & Filed this 6 day of
Dec. 1995 at 11:47 A M

Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Thomas P. O'Brien in a field survey on Nov. 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- G-13 (S.E. Corner Sec. 33)
Aug. 6, 1845 John Burt D.S. set corner post.
Tamarack 4 N51W 12 W. Pine 10 N42E 37
- Sept. 9/45 John Burt D.S. South between sections 3&4.
Tamarack 5 S13W 12 do 5 S76E 52

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-13 Aug. 5, 1976 Thomas P. O'Brien, RLS set 1/2" iron rod with RLS # 21274 cap by single proportion between E-1 & M-1.
- June 30, 1983 Donald R. Schofield, RLS found 1/2" iron pin with bearing tree with metal plate of county surveyor.
- Oct. 17, 1994 Thomas P. O'Brien, PS recovered 1/2" iron rod as set by Thomas P. O'Brien.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-13 1/2" iron rod w/RLS21274 cap set in monument box.
- witnesses:
- 6" Tamarack N19°W 73.70'
- 8" Tamarack N34°E 97.0'
- Power Pole S30°E 58.20'
- Post S4°W 50.0'



Signed by Thomas P. O'Brien
Thomas P. O'Brien, PS

Date Dec. 4, 1995

Surveyor's Michigan License No. 21274