

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

DATE 12/10/96 <sup>005</sup>

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
MEMORUMENTATION

MAY 13 1997

COMMISSION

For corners in

Schoolcraft Located In: Corner Code #  
(County)

- |                                    |                             |       |
|------------------------------------|-----------------------------|-------|
| 1. Public Land Survey              | T <u>42</u> N R <u>15</u> W | H-9   |
|                                    | T ___ R ___                 | _____ |
|                                    | T ___ R ___                 | _____ |
|                                    | T ___ R ___                 | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___           | _____ |
|                                    | S ___ T ___ R ___           | _____ |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___           | _____ |
|                                    | S ___ T ___ R ___           | _____ |

Received & Filed this 18th day of  
December 1996 at 3:08 P. M

Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien in a field survey on Dec. 16, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		13		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-9 ( N 1/4 Corner Sec. 27)  
Sept. 13, 1850 - Algernon Merryweather D.S. set qr. section post.  
Balsam 4 in. N55E 14 links do. 6 in. S20W 16 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9 June 30, 1983 Donald R. Schofield, RLS set 3/8" reinforcing bar 18" with cap at " proportionate measurement between G-9 and I-9."

Dec. 16, 1996 - Thomas P. O'Brien, P.S. recovered 3/8" iron rod w/Schofield cap# 25871. Set Schoolcraft County monument 5.65' East of Schofield corner at single proportionate measurement between G-9 and I-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9 Schoolcraft County monument stamped to identify.

Witnesses:  
6" Cedar - N5°W - 11.78'  
8" Cedar - N41°E - 10.50'  
6" Cedar - S19°E - 46.71'  
10" Cedar - S28°W - 41.53'  
4" Cedar post - North - 2.0'

*Thomas P. O'Brien*

Signed by Thomas P. O'Brien

Date Dec. 16, 1996

Surveyor's Michigan License No. 21274

