

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

DEC 18 1996

DEC 21 1996

DATE 9/13/96

COMMISSION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft
(County)

Located In:

Corner Code #

1. Public Land Survey

T42NR15W

I-1 ✓
I-13

T43NR15W

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Received & Filed this 30 day of
Oct 1996 at 11:33 AM

Sigrid J. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on Aug. 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-1 (N.W. Corner Sec. 2)
May 30, 1841 William A. Burt D.S. set corner post.
Tamarack 14 N51E 17 Spruce 8 N68W 4

Sept. 17, 1850 Algernon Merryweather D.S. Corner 2&3 North Boundry.
Cedar 16 in. S75E 23 lks. Cedar 12" S40W 43"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 May 22, 1961 - Billy D. Buckler RLS set a 1" pipe with 4" brass cap.
Corner was re-established by single proportionate measure from corners
1/2 mile East and 1 1/2 miles West.

Aug. 20, 1996 Thomas P. O'Brien P.S. recovered a 1" pipe with 4" brass cap as set by Billy D. Buckler on May 22, 1961.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 Aug. 20, 1996 Thomas P. O'Brien P.S. recovered Michigan Dept. of Cons.
1" pipe with 4" brass cap stamped to identify.

Witnesses: Fd 12" Cedar - N53°E- 31.23' Ex. Cond.
Fd 10" Cedar - S80°E- 16.55' Ex. Cond.
Fd 7" Cedar - S76°W- 10.37' Ex. Cond.
8" Cedar - North- 31.68' NBT
4" Cedar Post N.W. 1.0'

Fd Register Tree facing corner in good condition.

Signed by Thomas P. O'Brien

Date August 20, 1996

Surveyor's Michigan License No. 21274

USER 4 PAGE 59

