

MAY 16 1987

COMMISSION

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

DATE 12/10/96 ^{JOB}

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Received & Filed this 18th day of
December 19 96 at 3:09 P M

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T42NR 15W	I-7
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on Dec. 10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7									X				
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-7 (N.E. Corner Sec. 22)
Sept. 14, 1850 - Algernon Merryweather D.S. set corner post.
Hemlock 34 in. S65E 33 links Birch 9 in. N52W 32 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-7 Dec. 10, 1996 - Thomas P. O'Brien, P.S. re-established corner by double proportionate measurement. No evidence of G.L.O. survey or subsequent restoration recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7 Schoolcraft County monument stamped to identify.

Witnesses: 8" Cedar - S57°E - 47.60'
10" Maple - S68°W - 67.18'
10" Maple - N74°W - 56.14'
8" Maple - N53°E - 52.07'
4" Cedar post - North - 4.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec. 16, 1996