

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED
DATE 12/10/96**

SURVEY &
REMONUMENTATION

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft
(County)

Located In:

Corner Code #

1. Public Land Survey

T42NR15W

I-10

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

Received & Filed this 30 day of
Dec. 1996 at 9:32 A.M.
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on Dec. 13, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-10 Sept. 13, 1850 - Algernon Merryweather D.S. set qr. section post.
Cedar 18 in. N75E 22 links Birch 24 in. South 9 links

Feb. 1987 - William F. Bowman, L.S. "re-established by survey on
line between I-9 & I-11 by proportionate measure."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 Dec. 13, 1996 - Thomas P. O'Brien, P.S. failed to recover Bowman
corner, witnesses insufficiently marked. Re-established corner by
single proportionate measurement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 Schoolcraft County monument stamped to identify.

Witnesses: 8" Cedar - N54°E - 110.90'
8" Cedar - S34°W - 55.48'
10" Cedar - N51°W - 116.35'
N.W. Building corner - S16°E - 17.98'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec. 26, 1996