

**SCHOOLCRAFT COUNTY**  
**PEER GROUP APPROVED**

SURVEY &  
 REVISION/IDENTIFICATION

DATE 9/13/96 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

NOV 2 1996

COMMISSION

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T42N R15W T43N R15W	J-1 ✓ J-13
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

Received & Filed this 30 day of Oct 1996 at 11:40 AM  
 Sigrid I. Hedberg  
 Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien in a field survey on March 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-1 (North 1/4 Corner Sec. 2)  
 May 30, 1841 William A. Burt D.S. set qr. section post.  
 W. Pine 14 N49E 61 Spruce 8 N23W 6

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 May 11, 1961- Billy D. Buckler, RLS set a 1" pipe with 4" brass cap.  
 "Corner replaced from one W. Pine bearing N 49 deg. E, 61 lks."

March 22, 1996- Thomas P. O'Brien P.S., recovered a 1" pipe with 4" brass cap as set by Billy D. Buckler on May 11, 1961.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 Found Mich. Dept. of Cons. 1" pipe with 4" brass cap stamped 1/4  
 $\frac{32}{5}$  restamped corner correctly  $\frac{35}{2}$ .

Witnesses: Fd. 18" Red Pine- S42°W - 29.85' Ex. Cond.  
 10" Red Pine- N77°E - 46.44' NBT  
 8" Red Pine- S60°E - 70.98' NBT  
 10" Red Pine- N62°W - 38.43' NBT  
 4" Cedar Post - North - 1.5'

*Thomas P. O'Brien*

Signed by Thomas P. O'Brien  
 Surveyor's Michigan License No. 21274

Date March 22, 1996

