

MAY 16 1937

COMMISSION

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED
DATE 12/10/96

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42</u> N <u>R</u> <u>15</u> W	<u>J-7</u>
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

Received & Filed this 30 day of
Dec 1996 at 9:30 AM
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on Dec. 6, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7										X			
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-7 Sept. 14, 1850 - Algernon Merryweather D.S. set gr. section post.
Cedar 12 in. N35W 15 links do. 14 in. S20E 13 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7 Dec. 6, 1996 - Thomas P. O'Brien, P.S. re-established corner by single proportionate measurement. No evidence of G.L.O. survey or subsequent restoration recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7 Schoolcraft County monument stamped to identify.

Witnesses: 3" Cedar - N73°E - 52.37'
6" Maple - S27°E - 40.03'
6" Birch - S39°W - 10.52'
3" Cedar - N51°W - 63.98'
4" Cedar post - South - 2.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec. 26, 1996